






APPROXIMATE
LOCATION OF PROPOSED PROJECT

CALIFORNIA STATE MAP
NOT TO SCALE

LOCATION OF PROPOSED PROJECT



LOCATION MAP
NOT TO SCALE



VICINITY MAP
NOT TO SCALE

INDEX	SHEET NO.
PROJECT LOCATION MAP	1 OF 6
SURVEY PLAN	2 OF 6
PLAN VIEW AND CROSS-SECTIONS OF GABION WALL	3 OF 6
PROFILE ALONG GABION WALL	4 OF 6
CONSTRUCTION DETAILS	5 OF 6
CONSTRUCTION DETAILS	6 OF 6

90% SUBMITTAL – NOT FOR CONSTRUCTION

Don't Dig...Until You Call
U.S.A. Toll Free 1-800-227-2600

for the location
of buried
utility lines.
Don't disrupt
vital services.
TWO WORKING DAYS BEFORE YOU DIG

GENTERRA
CONSULTANTS, INC.
Engineering & Geotechnical Services
Irvine, California

DESIGNED BY: SB/SL
DRAWN BY: SL
DATE DRAWN: OCTOBER 2022
CHECKED BY: JJK

BENCHMARK:

REF.	DESCRIPTION	APPR.	DATE	APPR.	DATE

REVISIONS		ENGINEER	STANFORD

PARADISE IRRIGATION DISTRICT

RECOMMENDED FOR APPROVAL BY:	APPROVED BY:
DATE: _____	DATE: _____


**MAGALIA DAM SPILLWAY
INTERIM RISK-REDUCTION REPAIR**

PROJECT LOCATION MAP

PROJECT NO.
391-PID-I

DRAWING NO.

SHEET NO.
1 OF 6



90% SUBMITTAL - NOT FOR CONSTRUCTION

Don't Dig...Until You Call
U.S.A. Toll Free 1-800-227-2600

for the location of buried utility lines.
Don't disrupt vital services.
TWO WORKING DAYS BEFORE YOU DIG

GENTERRA
CONSULTANTS, INC.
Engineering & Geotechnical Services
Irvine, California

REGISTERED PROFESSIONAL ENGINEER
JOSEPH J. KULIKOWSKI
No. 17478
CIVIL
STATE OF CALIFORNIA

DESIGNED BY: SB/SL
DRAWN BY: SL
DATE DRAWN: OCTOBER 2022
CHECKED BY: JJK

BENCHMARK:

REF.	DESCRIPTION	APPR.	DATE	APPR.	DATE

REVISIONS	ENGINEER	STANFORD

PARADISE IRRIGATION DISTRICT


RECOMMENDED FOR APPROVAL BY: _____ DATE: _____

APPROVED BY: _____ DATE: _____


MAGALIA DAM SPILLWAY
INTERIM RISK-REDUCTION REPAIR

SURVEY PLAN


PROJECT NO. **391-PID-1**
DRAWING NO. _____
SHEET NO. **2 OF 6**



PLAN VIEW OF GABION WALL



CROSS-SECTIONS OF GABION WALL



PROFILE OF GABION WALL AND EXISTING RIGHT SIDE SPILLWAY WALL



90% SUBMITTAL – NOT FOR CONSTRUCTION



GENTERRA
CONSULTANTS, INC.
Engineering & Geotechnical Services
Irvine, California



DESIGNED BY: SB/SL
DRAWN BY: SL
DATE DRAWN: OCTOBER 2022
CHECKED BY: JJK


BENCHMARK:

REVISIONS		ENGINEER		STANFORD	
REF.	DESCRIPTION	APPR.	DATE	APPR.	DATE


PARADISE IRRIGATION DISTRICT	
RECOMMENDED FOR APPROVAL BY:	APPROVED BY:
DATE:	DATE:

MAGALIA DAM SPILLWAY
INTERIM RISK-REDUCTION REPAIR
PROFILE ALONG GABION WALL


PROJECT NO. **391-PID-1**
DRAWING NO. **4 OF 6**
SHEET NO. **4 OF 6**





REINFORCING DETAILS



CORNER STIFFENER



TYPICAL DIMENSIONS AND NAMING CONVENTION






STANDARD GABION SIZES				
LENGTH	WIDTH	HEIGHT	NUMBER OF DIAPHRAGMS	VOLUME
				CY
6'-0"	3'-0"	3'-0"	1	2.0
9'-0"	3'-0"	3'-0"	2	3.0
12'-0"	3'-0"	3'-0"	3	4.0

- NOTES:
- Internal connecting wire (13.5-gage) to be installed across width of interior gabions and across width and length of end gabions.
 - Internal connecting wires (cross-tie wire) required on all gabions 3'-0" high.
 - Place rock in end gabion cell first, and continue by filling interior gabion cells.
 - For gabion dimensions, refer to table "Standard Gabion Sizes".
 - Bottom gabion layer should be anchored to the spillway slab.
 - Back gabion cells that will be located immediately adjacent to the right wall should be anchored to the wall.

NOT TO SCALE

90% SUBMITTAL – NOT FOR CONSTRUCTION






ALTERNATIVE GABION JOINT MATERIAL FASTENERS

(Fastener dimensions nominal)
(See Note 3)


- NOTES:

1. A joint connection must be made where any panel edge meets another panel. This includes adjacent gabion baskets, individual panels within a basket, diaphragm edges, etc.
2. Standard tie wire may be used as a joint connector for either twisted or welded mesh. Spiral binder is to be used with welded mesh only.
3. When alternative gabion joint material fasteners are not capable of enclosing all wires along a joint, especially at Basket-To-Basket Joints, either standard tie wire or spiral binder, as applicable, must be used.



- To Assemble Transitional Gabion Basket:

- Step ① Cut mesh along joint between Front Panel and Base Panel.
- Step ② Unfasten End Panel "A" from Base Panel and rotate End Panel "A". Fasten End Panel "A" to Back Panel.
- Step ③ Fold the cut portion of the Base Panel into upright position along diagonal from the diaphragm to the corner of the Back Panel.
- Step ④ Fold the Back Panel, Front Panel and End Panel "B" into upright positions. Fasten End Panel "B" to the Back Panel and the Front Panel.
- Step ⑤ Rotate End Panel "A" and the cut portion of the Front Panel inward against the upturned portion of the Base Panel. Fasten along the overlapped portion of the Front Panel and End Panel "A". Fasten the overlapped portion of the Front Panel and End Panel "A" to the folded upright portion of the Base Panel along the diagonal (described in Step 3).
- Step ⑥ Fill the Transitional Gabion Basket with rock as per specifications.
- Step ⑦ Close lid and fold over corner of Lid Panel. Fasten along Lid Panel edges.



NOT TO SCALE

TRANSITIONAL GABION BASKET

(For 6'-0", 9'-0" or 12'-0" Length Gabion)

90% SUBMITTAL – NOT FOR CONSTRUCTION



GENTERRA
CONSULTANTS, INC.
Engineering & Geotechnical Services
Irvine, California



DESIGNED BY:	SB/SL
DRAWN BY:	SL
DATE DRAWN:	OCTOBER 2022
CHECKED BY:	JKK

BENCHMARK:

	REVISIONS	ENGINEER		STANFORD	
REF.	DESCRIPTION	APPR.	DATE	APPR.	DATE

PARADISE IRRIGATION DISTRICT

RECOMMENDED FOR APPROVAL BY:

APPROVED BY:

DATE: _____

DATE: _____

MAGALIA DAM SPILLWAY INTERIM RISK-REDUCTION REPAIR	1	1	1
---	----------	----------	----------

CONSTRUCTION DETAILS

PROJECT NO.	391-PID-I
DRAWING NO.	
SHEET NO.	6 OF 6